



ELECTRIC POWER  
RESEARCH INSTITUTE

## Industry Zinc Injection Update

**2010 ISOE North American ALARA  
Symposium / EPRI Radiation Protection  
Conference**

January 2010

David Perkins  
Program Manager  
Carey Haas  
Project Manager



Supporting Material Provided By Jeff Deshon  
and Dennis Hussey

# EPRI Studies – Effect of Plant Design and Chemistry on Shutdown Releases and Dose Rates


- Understood or Key Factors To Consider on Shutdown Releases and Dose Rates:
  - EFPY
  - Steam Generator Area, Materials and Surface Finish
  - Core Duty
  - Chemistry - pH<sub>T</sub> and Zinc Addition
- Other Factors to Consider Related to Shutdown Release
  - Steam Generator Manufacturing Process
  - Plant Operations – Cycle Length, Mid-Cycle Outages, Trips, etc
  - Fuels (other Factors)
    - Ultrasonic Fuel Cleaning
    - Surface Area, etc
  - Shutdown Chemistry Evolution
    - Example: Reactor Coolant Pump Operation
- Chemistry Controls
  - EOC Boron
  - pH Program
  - Letdown and Cleanup
  - Zinc Injection
    - Zinc Injection continues to show a positive impact on dose rates.
    - Reductions in steam generator and piping dose rates were routinely observed following zinc addition with over 80 cycles of data collection efforts.

# What Can The Chemist Impact With So Many Variables?


## Challenges Associated with Dose Reduction Efforts

Thursday, January 07, 2010

Chemistry Controls




# Current Status on Zinc Injection



# Pressurized Water Reactor (PWR) Zinc Injection Experience Growing Worldwide

Worldwide PWR Zinc Injection  
Actual and Projected



# An Overview of the EPRI Zinc Program



A comprehensive zinc program focused on chemistry, materials, fuels and radiation management with an open forum focusing on industry activities :

- Radiation Field Management - Radiation Protection Program
  - Standardized monitoring approach (SRMP)
  - Collecting, maintaining and evaluating industry data for zinc and non-zinc plants
- Primary Water Stress Corrosion Cracking (PWSCC) Benefits - Materials Reliability Program
  - Potential chemical mitigation option for PWSCC
    - Initiation and/or mitigation
    - Inspection
  - Combined benefit with elevated RCS Hydrogen
- Fuel Performance – Fuel Reliability Program
  - Corrosion Product Management
  - High duty cores
  - CRUD changes

# Zinc Injection – Fuel Performance

## EPRI Fuel Reliability Program Objective

To ensure fuel integrity and performance are not challenged from zinc injection.

## Approach

- Methodical – theoretical / laboratory / plant demonstration
  - Apply zinc at low duty units first and transition to higher duty plants



Plant Demonstrations: Increasing Fuel Duty

Farley » **Diablo Canyon** » **Callaway** » **Vandelllos II** » **Braidwood/Byron 1**

EPRI Sponsored Fuel Surveillances



# PWR Zinc Application – Fuel Performance

## History

- Over 6500 ppb-months exposure in the current database.
- M-5™ Cladding Exposure is increasing.
- Zirlo™ has the most exposure in the industry database with over 5700 ppb-months exposure.
- Zinc addition modeling tool developed for fuel assessments

## Some Conclusions to Date

- Zinc has not caused an increase in fuel cladding corrosion at any of the EPRI sponsored campaigns or others that we are aware of.
- No abnormal buildup of crud has been observed
- No fuel performance issues (i.e. AOA, IRI) have been linked directly to zinc injection



# Strategy for Applying Zinc in PWRs

## What have we learned?

### Historical Concerns with Zinc Injection

1. Zinc injection has been observed to cause step increases in coolant **radiocobalts** – suggesting that transition metals would also increase
2. Biblis B and Unterweser reported elevated **Fe** concentrations upon injecting zinc
3. Zinc crud in BWRs is known to be more **tenacious** than non-Zn deposits and contains up to **35 wt% zinc**
4. **Zinc silicate** was measured in deposits in the SNB region of the fuel stack at a U.S. BWR


### EPRI Fuel Reliability Program Zinc Program Observations

1. Increases in **radiocobalts** have been observed at many plants while little or no increases have been observed at some.
2. No increase in **Fe** or **Ni** was observed at Vandelllos II in either Cycle 15 or 16 - Alloy 600TT SG tubes
3. No **tenacity** information, but thus far the highest measured zinc fraction contained in PWR crud is **~7.5 wt%**
4. No **zinc silicate** (or Zn ferrite) has been measured in any of the FRP-sponsored plant demonstrations, nor have any such deposits been reported from other PWR campaigns

# Zinc Injection – Materials and PWSCC

- Zinc has shown to date to be compatible with all RCS materials
- Zinc continues to show benefits for reduction of PWSCC initiation
- Little or no improvement in mitigation of crack growth rate for thick walled components
  - Looking at combined effect with elevated RCS hydrogen for chemical mitigation
  - Some benefit seen for steam generator tubes

# Zinc Injection – Chemistry





## Chemistry Impact

- Apparent reduced zinc demand as zinc exposure increases
- Plants routinely show a reduced zinc demand after 2 – 3 cycles of injections

## Continued Evaluations...

- Is there an equilibrium or amount of zinc that utilities can adjust their program and maintain effect?
  - Maintenance Program vs. Injection Program
- Quantify impacts of cycle to cycle changes
  - Core design changes
  - New RCS materials



# Zinc Injection – Chemistry



## Chemistry Impact

- Observation:
  - Variable chemistry response to zinc addition
    - Nickel and iron trends vary by plant and materials

## Continued Evaluations ..

- Impact of
  - steam generator replacement
  - corrosion products with high duty cores
    - Alloy 600 vs. 690 vs. 800
  - Combined with Elevated pH Program or Elevated Hydrogen Program
  - Cycle Changes

<i>Material</i>	<i>Corrosion</i>		<i>Corrosion Release</i>	
	<i>with Zn</i>	<i>w/o Zn</i>	<i>with Zn</i>	<i>w/o Zn</i>
600 MA	1.5	2.6	0.3	0.8
600 TT	0.5	2.1	0.2	0.9
690 TT	0.2	1.3	0.1	0.6

# Zinc Injection – Radio-Cobalt Trends




## Chemistry Impact


- In general plants may observe a factor of 8 to 10 times increase in cobalt levels compared to pre-zinc levels
  - In several cases plants have not observed any increase
  - In at least one case a factor of 1000 increase was observed

## Continued Evaluations...

- Why the difference and is it related to materials (i.e. SG tubing, etc.)...
- Is it related to core design ...




# Zinc Injection – Radio-Cobalt Trends




## Chemistry Impact

- There have been 2 units that showed a different trend.
  - Co-58 increased to greater than 0.1  $\mu\text{Ci/ml}$  and stayed elevated for duration of cycle.



# Zinc Injection – Shutdown Releases




## Impact on Shutdown Release

- No clear correlation of zinc exposure on peak post peroxide  $^{58}\text{Co}$  concentration for Alloy 690 or Alloy 600 plants
- Alloy 690TT plants peak  $^{58}\text{Co}$  concentrations appear slightly higher than for Alloy 600 plants.

## Continued Evaluations ...


- Assess differences in shutdown releases for zinc and non-zinc plants to be able to estimate impact of long term zinc injection





# Dose Rates: Effect of Zinc On Channel Head Dose Rates


- Most plants start to see a reduction in dose rates following the first cycle of injection
- The dose reductions observed are consistent with expectations and the industry database



# Dose Rates: Effect of Zinc On Loop Dose Rates



- Loop dose rates follow a similar trend and reductions can be observed in most cases following the first two cycles of injection.



# Zinc Injection Guideline – Dose Rates




## Dose Rate Trends


- Long term injection continues to show a dose reduction benefit.

## Continued Evaluations ...

- Zinc injection using depleted zinc and affect of transition to depleted from “natural” zinc
- Root cause assessments of unexpected results
  - Initial Bugey and Biblis cycle results
  - Impact of power transients during the cycle on dose rates (Palisades)?
- Load-follow plant operation results with zinc injection



# EPRI Zinc Addition Program Schedule



# Zinc Injection

## Current Status

- Over 25% of the fleet pressurized water reactors will be injecting zinc within the next 2 years.
- Zinc injection is not a “Fad” or “Flavor of the Month” but a viable option for plant chemist as part of an overall integrated strategy.
- Zinc injection has shown to reduce dose rates after the first 1 – 2 cycles of injection
- Low, medium and high duty are Injecting and to date there has not been fuel performance related issues
- Zinc Injection shows a favorable impact on PWSCC crack initiation