

ISOE Working Group on Radiological Protection Aspects of Decommissioning Activities at Nuclear Power Plants (WGDECOM) – Outcomes and feedback

Laure-Anne BELTRAMI on behalf of WGDECOM

ISOE International Symposium

Beijing, 22nd October 2019

Background and objectives of ISOE WGDECOM

- Decommissioning of NPPs is a subject of growing importance for the nuclear industry and meets some economical, technical and organisational challenges. WGDECOM created in 2014.
- Membership: 30 members from 13 countries from NPPS in decommissioning or in preparation for decommissioning
- **Objective:** improve sharing of operational RP data and experience collected through benchmarking visits (1 to 2 per year) in NPPs under decommissioning
- Topics of interest:
 - Areas of RP most relevant for management of occupational exposure.
 - Collection of operational data
 - Create a **network** of operational RP experts for decommissioning activities
 - Factors and aspects that play key roles in achieving **good RP practices** in decommissioning.

Topics discussed during WGDECOM meetings

- Regulatory context and decommissioning strategy
- Transition phase
- Collective doses analyses for high dose works
- Management of risk of internal exposure
- Radioactive waste management
- Integrated risk management

- **Immediate dismantling** (France - from 2000, Switzerland, Spain, Sweden and USA)

- **Deferred dismantling** (Spain, Sweden and USA): plants in safe store after removal of nuclear fuel and kept under surveillance for a period depending on the site: 20 years at Barsebäck, 50 years at Kewaunee.
Allows:
 - => Decay of some radionuclides
 - => Decrease of radiological exposure
 - => Option generally selected for economical and technical issues

- Key factors for success of decommissioning project :
 - **Characterisation** strategy

 - Determine **beginning** of decommissioning work

 - **Organisational** aspects to be considered in transition phase, in particular:
 - Evolution of organisation to adjust to decommissioning specificities
 - Need for a cultural change of management and operators to take into account the decrease of personnel, the integrated risk management, general RP culture, etc.
 - Changes of regulatory requirements between operation and decommissioning

Collective doses for decommissioning (1)

- Are not linked to power of reactors

Country	Site	Type and power	Safe storage	Decom. duration	Dose
Spain	Jose Cabrera	PWR 160 MWe		10 years	2,7 H.Sv
	Vandellos 1	GCR 500 MWe	15 years	5 years	0,4 H.Sv
USA	San Onofre 1	PWR 450 MWe	8 years	17 years	3 H.Sv
	Zion 1 & 2	PWR 1100 MWe	10 years	7 years	4,4 H.Sv

- Collective exposures easily reach a few man.Sv per reactor
=> some hundreds of mSv per year of dismantling : more than some annual outage doses for operational reactors

Collective doses for decommissioning (2)

ACTIVITIES	Collective dose (mSv-p)	
Plant Modifications & General Works	157,84	5,8%
Maintenance & Surveying	384,16	14,2%
<u>Main Components</u>	846,00	31,3%
In situ decontamination(tanks/components)	31,96	1,2%
Spent Fuel Pool conditioning & decontamination	95,79	3,5%
Components dismantling - Containment building	197,47	7,3%
Components dismantling - other buildings	266,43	9,9%
Biological shielding	141,79	5,2%
Contaminated concrete removal	316,92	11,7%
Walls & floors decontamination	36,07	1,3%
Decontamination workshop	29,38	1,1%
Rad Waste management	199,12	7,4%
Site restoration	0,00	0,0%
<i>total</i>	2702,93	




Collective dose (mSv-p) by activity (main components splitted)



ACTIVITY:		Collective Dose mSv	Man- h
SURVEILLANCE & MAINTENANCE		384,16	191550
02 - SURVEILLANCE & MAINTENANCE		H-p	Dosis µSv-p
02-01	Occupational Health & Safety	11443	16251
02-02	Medical Services	58	104
02-03	Instrumentation Maintenance	4294	9982
02-04	Mechanical Maintenance	6136	26270
02-05	Electrical Maintenance	4403	10254
02-07	Security	1440	1032
02-08	Radiation Protection	69444	204044
02-09	Fire Protection	13283	6532
02-10	Decontamination & Housekeeping	73890	104538
02-11	General Services	5883	5155
			Tdp_µSv/h
			1,4
			1,8
			2,3
			4,3
			2,3
			0,7
			2,9
			0,5
			1,4
			0,9

Collective doses for decommissioning (3)

ACTIVITY:		Collective Dose mSv	Man-h
Main Components_STEAM GENERATOR		329,71	12090
05 MAIN COMPONENTS : Steam Generator			
	H-p	Dosis μ Sv-p	Tdp_ μ Sv/h
05-04	Scaffolding	704	4143
05-05	Isolation removal	278	2655
05-06	Stem pipe removal	364	1381
05-07	Water supply pipe removal	163	815
05-08	Instrumentation removal	104	796
05-09	Steam section removal	1294	6191
05-10	Supports removal	551	4724
05-13	Confinement & filtration equipment	187	1006
05-14	SG Segmentation in situ	8605	276252
05-16	SG Segmentation in the SAS	657	31742



Management of risk of internal exposure

- **Higher risk** of internal contamination in decommissioning than in operational plants.

- Surface contamination:
 - Decommissioning plants: **dry contamination**
 - Operational plants: wet contamination

- Specific attention to the management of collective and individual protective equipment

- Evaluation of risk of **alpha** contamination and specific management

- Significant impact on decommissioning project
- Possibility of **clearance** of some materials with a very low level of radioactivity taken into account in waste management plan except in France and USA.
- **Temporary storage** of high level radioactive wastes on site due to lack of disposal

- **Final end-state:** essential input to define decommissioning plan

- **Complex** and evolutive environment:
 - Asbestos, lead
 - Heavy load transport
 - Cutting works
 - Works at height
 - ...

- A lot of **simultaneous works** that can induce complementary risks

- Huge challenge for RP staff

- Example France: difficulty of management of works in a contaminated area (alpha) with asbestos. In France, there is **no common regulation** for management of these two risks:
 - **Asbestos**: Use of water to remove contamination and decrease quantity of asbestos dust during work with asbestos,
 - **In controlled areas**, avoid use of water:
 - Can spread the contamination,
 - Production of liquid radioactive effluents,
 - Production of radioactive wastes containing asbestos,
 - Not possible to monitor alpha emitters...
 - French utilities proposal: use of a red surfactant instead of water to fix asbestos and identify transfer of contamination during undressing.

- **Historical knowledge** of the site has to be known to define decommissioning strategy and assess relevance of actions during transition phase
- Assessment of **contamination** levels and associated radiological spectrum for purposes of RP and waste management.
- Use of **adapted** technologies and operating procedures: works in complex environment with management of highly radioactive materials and address difference of organisation factors with operational phase
- Need of a **specific training** of workers and RP technicians

- Importance of **transition phase** for the success of the project: characterization and evolution of organisation
- **Waste management** and **final end-state** identified as driving factors of the overall decommissioning project.
- Identify requirement for RP staff and workers skills (contamination) to maintain **RP culture** to adequate standards,
- **Integrated** approach for a relevant risk management
- **Collective doses** from decommissioning not linked to unit power and may not be negligible

Thanks for your attention