THE EFFECTS OF ZINC INJECTION FROM HOT FUNCTION TEST AT TOMARI UNIT 3

2014 ISOE Asian ALARA Symposium
September 23-24,2014

Presented by：Keisuke Sasaki
Hokkaido Electric Power Co., Inc.

Contents

- Introduction to TOMARI NPS
- Zinc injection
- Experiences of 1st cycle
- Experiences of 1st refueling outage(RFO)
- Experiences of 2nd refueling outage(RFO)
- Conclusion

Introduction to TOMARI NPS

	Unit 1	Unit 2	Unit 3
Rated Electric Output	579MW	579MW	912MW
Reactor type	PWR		
Commercial Operation	1990	1992	2009
SG	600TT	600TT	690TT
Letdown flow	20m³/h		54m³/h



Introduction to TOMARI NPS

- Operated History of Unit 3



Zinc injection

- Zinc injection during power operation



No zinc injection **Zinc injection**

- Substitution of zinc for Co
- Suppression Co uptake into the inner oxide layer

Zinc injection

- Zinc injection from HFT



Zinc injection during power operation

Zinc injection from HFT

- Suppression Co uptake into the inner oxide layer
- Corrosion suppression

EXPERIENCES OF 1st CYCLE

Zn concentration in the primary coolant



- Zinc concentration was controlled with the target concentration (5±3ppb).

EXPERIENCES OF 1st CYCLE

Ni concentration in the primary coolant



- Ni concentration was higher than that of the reference plant.

  ⇒ Ni releases from corrosion products and the base metal of SG tube.

EXPERIENCES OF 1st CYCLE

Co-58 concentration in the primary coolant



- The Co-58 concentration was higher than that of the reference plant.

  ⇒ Suppression Co uptake into inner oxide layer

EXPERIENCES OF 1st RFO

Concentrations of radioactive Co-58（Ion,Crud）in the primary coolant



- The particulate Co-58 was higher than that of the reference plant. The ionic Co-58 was at the same level as that of the reference plant.

  ⇒ The amount of the corrosion product with a higher specific radioactivity has decreased.

EXPERIENCES OF 1st RFO

Amount of Ni,Co-58,and Co-60 removal

	Tomari unit 3	Reference plant
Ni (g)	3039	3639
Co-58 (Bq)	1.3×10^{14}	1.2×10^{14}
Co-60 (Bq)	8.0×10^{11}	5.2×10^{11}

- The amount of Ni removal was about 20% less than that of the reference plant.

  ⇒ **Corrosion suppression effect**

- The amount of Co-58 removal was about equal to that of the reference plant.

  ⇒ **Suppression Co uptake into the inner oxide layer and decreasing Ni inventory**

EXPERIENCES OF 1st RFO

Dose-rates on SG tube, SG CH,RV Inside, and MCP



- The dose-rates at SG , RV inside and MCP were about over 40% less than those of the reference plant.

  ⇒ **The dose-rate reduction effect with zinc injection is about 40-60% at the 1st RFO.**

EXPERIENCES OF 1st RFO

- **Evaluation of Radiation Source Inventory [TBq]**

	Tomari unit 3	Reference plant
Co-58 inventory	22.2	43.2
Co-60 inventory	0.9	2.1
Radiation source inventory	**24.2**	**48.1**

- The Co-58, Co-60 and radiation source inventory were about 50% less than those of the reference plant.

  ⇒ **These are in good consistency with the actual dose-rates on the main components.**

EXPERIENCES OF 2nd RFO



- The dose-rates on SG tube, SG CH and RV Inside at the 2nd RFO were about 50-60% less than those at the 1st RFO.



- The dose-rates on MCP at the 2nd RFO were about 20-60% less than those at the 1st RFO.

CONCLUSION

- ✓ At the 1st RFO, the dose-rates at the main components are about 50% less than that of the reference plant, as a similar trend to the radiation source inventory.
- ✓ Considerable dose-rate reduction at the 2nd RFO was confirmed compared to the 1st RFO.
- ✓ From now on, further dose-rate reduction effect is expected.

Thank you for your Attention.

ともに輝く明日のために。
Light up your future.
ほくでん

MITSUBISHI HEAVY INDUSTRIES, LTD.
Our Technologies, Your Tomorrow