


Pressurizer Heater Nozzle Replacement at San Onofre

Kelli Gallion


NATC ALARA Symposium

January 2005




Discovery

- Planned to test two Alloy 600 heater sleeves
 - Both heater sleeves showed longitudinal indications above the J-weld
 - One heater sleeve showed a circumferential indication above the J-weld
 - No through wall indications and no leakage detected




Decision

- ❖ Replace all pressurizer heater sleeves during current U3 RFO
 - ❑ Conservative decision
 - ❑ Thirty heaters in pressurizer
 - ❑ Replace sleeves with Alloy 690
 - ❑ Complete replacement precludes a forced outage due to leakage prior to C14 RFO
 - ❑ See INPO OE 19405
- ❖ Project originally scheduled for C14 RFOs.




Some Alloy 600 Characteristics

- ✿ Subject to primary water stress corrosion cracking (PWSCC)
 - ▣ Typically a long incubation period (up to 27 years)
- ✿ PWSCC depends on:
 - ▣ Operating temperature
 - ▣ Heat treatment
 - ▣ Cold work
 - ▣ Chemical environment
- ✿ All Alloy 600 heats used in U.S. plants have been tested for PWSCC and failed (EPRI)




Locations Where Alloy 600 PWSCC Has Occurred

- ⊕ Reactor head nozzles
- ⊕ Reactor vessel safe ends
- ⊕ Hot leg nozzles
- ⊕ Steam generator drains
- ⊕ Pressurizer heater sleeves
- ⊕ Pressurizer water and vapor space instrument nozzles




Major Project Evolutions

- ✚ Scaffold Erection (17' to 40')
- ✚ Determ/Reterm Heaters
- ✚ Remove/Replace Insulation
- ✚ Install Heater and Surge Line Shielding
- ✚ Cut Heater Seal Weld
- ✚ Remove Heaters
- ✚ Cut, Remove ½ of Sleeve




Major Project Evolutions Cont'd


- ❖ Install Sacrificial Plugs
- ❖ Temper Bead Pad Preparation
- ❖ Machine Pads, Remove Plugs
- ❖ Install New Inconel 690 ½ Sleeve
- ❖ New Pressure Boundary Weld
- ❖ Install New Heaters and Seal Weld
- ❖ Heater Cut Up and Disposal



Repair Process Diagram




15




Radiological Protection Challenges

- ⊕ Any Prior Experience?
 - ⊞ Palo Verde provided great assistance
- ⊕ Workers in Close Proximity to Heater Sleeves and Surge Line
 - ⊞ 100-300 mR/hr contact with sleeves
 - ⊞ ~60 mR/hr general area
- ⊕ 100s of mrad/hr smearable on heaters
- ⊕ Potential for high airborne
- ⊕ Inexperienced rad workers




Radiological Controls

- ⊕ Tent the pressurizer skirt
- ⊕ Maintain work platform at 10-50K dpm
 - ⊞ Permitted single coveralls, reduced heat stress
- ⊕ Extensive use of remote monitoring
 - ⊞ Personnel (dose, voice, video)
 - ⊞ AMS 4 air sampler
- ⊕ Bubble hoods for heater removal, full face respirators for external sleeve cuts, face shield/dust mask for other work
- ⊕ Two 1600 cfm HEPA and one HEPA vacuum for airborne control



Temporary Shielding

- Clam Shell Shield Over Heater Sleeves Until Heater Removed
- Lead Blankets Placed Around Surge Line
- Lead Blankets On Work Platform To Lower Exposure Rate In Area Used To Change PCs, and Control Work



Pre & Post-Shielding Dose Rates

☛ Sleeve Shields


- ~300 mR/hr contact, 180 mR/hr at 30 cm to
- ~120 mR/hr contact, 80 mR/hr at 30 cm

☛ Surge Line Shielding

- ~140 mR/hr contact, 60 mR/hr at 30 cm to
- ~50 mR/hr contact, 50 mR/hr at 30 cm


☛ Platform Shielding

- 20-60 mR/hr (knees to head) under pressurizer
- 5-12 mR/hr inside platform work/change area




Bottom of Pressurizer, Heaters Still Installed







Heater Shielding






Weld Pad Preparation





Radiation Exposure

- ⊕ Initial Estimate = 81.5 p-rem
- ⊕ Actual Dose = 64.9
- ⊕ 47 Dose Extensions > 1 rem
- ⊕ Highest Individual Dose = 1685 mrem
 - ⊞ Dosimeter located on head for most work due to overhead radiation source
- ⊕ RWP hours = 18,700
- ⊕ Job duration = 53 days




Personnel Contaminations and Intakes

✚ Contaminations

- ▣ 40 for workers
 - 16 were “planned”
- ▣ 9 for HP coverage
- ▣ 4 for scaffolding work

✚ Intakes

- ▣ 2 for workers
- ▣ 1 for HP coverage



Lessons Learned

- ❖ Poor scaffold platform
- ❖ Inexperienced workers yielded poor rad worker practices
- ❖ Poorly secured heater dropped after cut
- ❖ Vendor weld equipment problems
- ❖ Unsuccessful effort to weld pads with pressurizer filled.