

2012 ISOE/NATC International ALARA Symposium

Ft. Lauderdale, FL



Patricia Robinson,(n,p) Energy, Inc.



Presentation Outline

- Introduction
- Brief Review Technology Origin
 - **❖ Los Alamos National Laboratory Polymer Filtration™**Science
- Engineering the Solution for <u>Each</u> Rx Type
 - PWRs
 - **❖ BWRs**
 - **CANDUs**
- Summary of Results



Who is Los Alamos N.L.?



- US DOE R&D Labororatory for Nuclear Technology
 - Discover science and technology, where challenges are solved for the Medicine, Space, National security and Nuclear Technology
 - \$4 Billion R&D Annual Budget
- Los Alamos N.L. Major Awards
 - * 118 R&D 100 awards since 1978
- Invented and Patented, Polymer Filtration Technology™
 - Exclusive World-Wide Grant of Licensed Inventions
 - R&D 100 Award-Polymer Filtration Technology
 - (n,p) Energy, Inc.- Single and Sole Licensee
 - ❖ NPE is <u>not</u> a Resin Vendor... We provide a 2 Part Engineered solution



Los Alamos N.L. ScienceR&D 100 AWARD Winner for Polymer Filtration Technology™

What Los Alamos Can do, depending on your need

Selective Capture and Removal of Specific Elements H He Blue Box: Selective Binding Capability of LANL Inventions Li Be C N 0 F Ne В Outlined Box: Relevant to NPP Mg Na ΑI Si P S CI Ar K Ni Se Ca Sc Ti Cr Fe Co Cu Zn Ga Ge As Br Kr Mn Pd Ag Rb Sr Υ Zr Nb Mo Tc Ru Rh Cd In Sn Sb Te Xe Cs Ba La Hf Ta w Re Os Pt Au Hg TI Pb Bi Po Rn Αt Fr Ra Ac

Се	Pr	Nd	Pm	Sm	Eu	Gd	Tb	Dy	Но	Er	Tm	Yb	Lu
Th	Pa	U	Np	Pu	Am	Cm	Bk	Cf	Es	Fm	Md	No	Lw



CY 2000: First of a Kind Engineered Solution Developed for US PWRs

- Early 1998... Collaboration Process Engaged
 - Florida Power and Light/ LANL/ NPE
- Florida Power and Light Turkey Point 3,4
 - Sponsored Research & Development -First of a Kind Engineering.
 - \$1.2 M Investment by Florida Power and Light
 - Developed Shutdown Sequence (Protocol) and PRC-01M Media



How is PRC-01M Integrated?

Existing Plant Systems CVCS, Fuel Pool, Boron Recycle

PWR: PRC-1 (bead) or BWR: PRC-2 (powdered)

Existing Plant Equipment

PWR: Uses CVCS Demin

Both: Spent Fuel Pool

BWR: Filter/Demineralizer


RWCU

FPC

Torus



BWR
Precoat Filter/Demin



PWR Deep Bed Vessel



Lead Plants NPE/PRC-01 Engineered Solution

- PWRs 3 Loops
 - Turkey Point-3,4
 - VC Summer
- PWR 4 Loops
 - **❖** DC Cook 1,2
- BWRs
 - **❖** Peach Bottom 2,3
 - Monticello
- Colmpleted > 120 Refueling Outages wit PRC-01/PRC-01M

- B&W:
 - Crystal River (First-Trial)
 - Davis Besse
- > CANDU:
 - ❖ Bruce A/B

Metrics and Measures Measurement Instruments **Dose Rates Baseline-CNTMT Monitors** Specific RWPs EDR SG- SRMP Rx Hd R-R Heat HX SG RWP Rx Head D.R **Effective** Component CNTMNT GA & "Baseline" **Dose Rate Dose Rates** Field Trials Gamma Spectrum **TLD Dose** ED TLD Buyback **Energy Emission CZT** Rate PCE's Gamma Pipewall Deposited # of LHRA/HRA PCE's DC Cook 1,2 **Activity Estimate Spectrum** & Benchmark LHRA/HRA **Data Options** Cycle **Fuel** Performance & **Duty & CIPS Forced Outages Outage** Fuel Duty **Execution of Shutdown Events CIPS** & Outage Plan **RFO Shutdown** Core Crud & Equipment & Cycle Shutdown Release Performance e.g CVCS Chemistry Demin & Filter Mass on Fuel Co-58, Ni Peak Analysis Zn/ No Zinc Cycle Co-60 Correlation with HL Dose Rates

Stranded Activity- LISV



QuickTime™ and a decompressor are needed to see this picture.





FPL 1st Integration 11 years Ago

#1 Turkey Point 3/2000, #2 St Lucie-1 4/2000 # 3 VC Summer













Turkey Point-3,4 & VC Summer Source Term Approach: Only Use of PRC-01

Turkey Point 3,4:

- Yes: Chemistry pH(t) = 7.1
- Yes: PRC-01 Media Technology
- ❖ No: Zinc, No Fuel Cleaning, No Elevated pH 7.2 to 7.4
- **❖ Fuel Duty: Middle Fuel Duty**
- 13 to 18 EFPY SG, Inconel 600 TT

VC Summer


- Yes: Chemistry pH(t) = 7.1
- Yes: PRC-01 Media Technology
- ❖ No: Zinc, No Fuel Cleaning, No Elevated pH 7.2 to 7.4
- Fuel: High Duty, AOA Susceptible
- ❖ 7 EFPY SG, Inconel 690 TT



FPL Turkey Pt-3R18 (1st PRC) RCS Shutdown Co-58

100 hrs to Clean-Up Goal


1 E-3 uCi/cc = 37 Bq/cc






FPL Turkey Pt-3 R20 (3rd PRC) Shutdown Co-58 70 Hours to Clean-Up Goal


1 E-3 uCi/cc = 37 Bq/cc






FPL Turkey Pt-3R21 (4th PRC) RCSP OOS Before Peroxide Injection Shutdown Co-58 56 Hrs to Clean-Up Goal

1 E-3 uCi/cc = 37 Bq/cc





Turkey Pt 3,4 & VC Summer Sustained, Predictable Decline in Co-58 & Co-60 Shutdown Peak




1 uCi/cc = 37 kBq/cc



Declining Co-58 and Co-60 at Power Reactor Coolant Concentrations


Long duration steady state cycles yield best results





Both Units...

Co-60 Decline at Power Drives Lower Containment Dose Rates for RFO





Effective Dose Rate Trending

Effective Dose Rate = <u>Total dose for the job</u> (mrem)


Total time for job (hour)

- Good Analysis Tool for RFO to RFO Comparison
 - Permits comparison between refueling outages with different scope of work in containment
 - Valid if shielding practice is consistent
 - Valid if methods are consistent
- RWP = Radiation Work Permit
- 1 mrem = 100 mSv



FPL Turkey Pt-3 Sustained Decrease in Outage EDR Overall Before/After PRC-01 = - 88.4%

1 mrem = 100 mSv






Reduced Volume and Curies for Waste Disposal

- Before
 - * ~10 RCS Filters / Cycle
 - 5 to 200 R/hr Vessel Dose Rate
 - * 1 R/hr = 10 mSv/hr
- > Now
 - 1 RCS / Cycle
 - ❖ 6 um RCS Filter
 - 200 mR/hr Dose Rate




Annual Liquid Effluent Discharges Co-58 and Co-60 Trend

Liquid Radwaste Processing System:
Activated Carbon, Conventional Resins- No Ultra-filtration or Reverse Osmosis







Annual Liquid Effluent Discharges Fe-55 and Ni-63





Ag-110m Decline





FPL Turkey Pt. 3,4 & VC Summer Successful Source Term Reduction Summary

- INPO Ranking Collective Exposure- Turkey Pt 3,4
 - 4th Quartile in 2000, Avg RFO 140 to 160 REM
 - 1st Quartile in 2006, 1 Unit top Decile, 52.7 REM
 - INPO Good Practice for Source Term at Turkey Pt 3,4 and St. Lucie 1,2
- INPO Ranking VC Summer
 - * 3rd Quartile 2000, 140 to 160 REM
 - 1st Quartile 2006, RFO16 52 REM TLD
- Effective Dose Rate Reduction
 - 93.3% reduction in effective dose rate for Containment RWPS
 - **❖** 90% reduction in EDR for all RWPs
- Avoided Occupational Radiation Exposure for multiple RFOs
 - 325 REM (3.25 Sv) estimated of avoided occupational exposure for Turkey Pt U3, same for U4 LLW Disposal Reduction Curies and Disposal Costs
 - \$250,000 USD avoided per RFO in primary resin curie surcharge for Low Level disposal
- Faster Shutdown Sequence
 - 26 hours earlier for last RCPs to be taken out of service (O/S)



Summary (cont.)

- 61.5%
 - Reduction in number of High Radiation Area
- **35%**
 - Reduction in contract HP staff, \$400,000 avoided costs every RFO.
- **76%**
 - Reduction in Hot Spots
- 49 X (fold)
 - Reduction in annual effluent activity discharged for Co-58 and 15 fold for Co-60
- 87.7 %
 - ❖ Reduction in Ni-63 annual effluent activity discharge, and 70% for Fe-55
- 1st World Record Low Dose Performance for U4 in 2005.
 - * 5.407 REM (54.07 mSv) U4 RVH
- 2nd World Record Low Dose Performance for U3 in 2005.





B&W Design


QuickTime™ and a decompressor are needed to see this picture.

2011: Davis Besse- RVH Planned 128 REM; Actual 58 REM RFO 16 to 17M - Two Core Rotations

Davis Besse EPRI Survey Data -Engineered Solution Implemented in RFO 15 16 RFO to 17M (12 Month)










CANDU: BRUCE POWER


Operations-Maintenance-Chemistry 7 Element Solution- Media is 1 Element


Only as Effective as Weakest Link



Discovery: Bruce BU7 Activity Transport Co-60 Increase 1,000 X, Sb-124 Increase 10,000 X

Bruce Power
Standard PHT
Ion Exchange Resin
Shows Almost No
Removal of
Co-60 or Sb-124
Entire Outage











Monticello R22 to R23 Results

PRC Use R22 RFO, Cycle, R23

April 2007


- **-28%**
 - Decline in BRAC Points
 - Main Circuit Piping- Standardized Locations
 - * 2003 to 2007: Declined 28.5 %
- **-38.5%**
 - Decline RPV Effective Dose Rate
 - ❖ R22: EDR =1.45 mRem/RWP-hr
 - **❖** R23: EDR = 0.89 mRem/RW-hr
 - **❖** Change: 38.5 %
- **-71.1 %**
 - Fuel Floor (Fuel Move/Inspection/CRB Replace)
 - * R22: 0.78 mRem/RWP-hr
 - ❖ R23: 0.21 mRem/RWP-hr
 - ***** Change: 71.1 %



Vermont Yankee R25 to R26 Results

PRC Use R25 RFO, Cycle, R25 May 2007

- **-28%**
 - Decline in A Recirc Suction
 - Main Circuit Piping- Standardized Locations
 - * 2005 to 2007: Declined 28.5 %
- **-48.%**
 - Decline IVVI RWP Dose
 - * 16.76 REM Planned IVVI RWP Dose
 - ❖ 8.172 REM Actual IVVI RWP Dose
 - ❖ Declined: -48%
- -43.4 %
 - Drywell RWP Dose
 - 21.21 REM Planned RWP Drywell Dose
 - ❖ 12.0 REM Actual RWP Drywell Dose



BWRs

- Application on RWCU
 - * 100% time
 - Refueling
- > Expanding to Flush in CPS
- Expanding to On-Line Portion of CPS




Questions?






Turkey Pt-3 Effective Dose Rate: Containment Stainless Steel Source Term

1 mrem = 100 uSv





Turkey Pt-3 EDR Auxiliary Bldg RWPs Show Co-60 Decay Rate






Benchmark Turkey Pt-3 & VC Summer

Avg. Channel Head Dose Rates Declining at Co-60 Decay Rate

17-21 EFPY Inconel 600TT vs. 3-7 EFPY Inconel 690






Surface Profile Stainless Steel

(J.Underwood Browns Ferry Photo)

- Colloids attach to surface under shutdown conditions if not mitigated
- Significant surface area for deposition
- Colloids can induce corrosion under specific conditions by creating an electrochemical cell





PWR Operating Experience Datawith PRC-1 Solution

Amount of Padioactivity

1 Bq =1 disintegration per second= 2.7 x 10⁻¹¹ Ci

Padiation Doca

	Amount o	I Kadioactivity	Radiation Dose
,	1 μCi —	37 kBq	0.1 mrem 1 μSv
-	27 μCi ——	1 kBq	1 mrem ———— 10 μSv
	1 mCi —	37 MBq	10 mrem ———— 100 μSv, 0.1 mS
	27 mCi	1 GBq	100 mrem 1 mSv
	1 Ci —	—— 37 GBq	1 REM ———————————————————————————————————
1	27 Ci —	1 TBq	10 REM — 0.1 Sv

1 US Gallon/Minute (GPM) = 3.785 L/Minute


SG Dose Rate, [R/hr]

Correct Science & Sequence, Yields Results


Correct with PRC-01 Integrated Solution
Wrong with Purolite A501P Anion Macroporous Resins

1 R/hr = 10 mSv/hr





Turkey Point-3 SG Dose Rates, Avg.





How Do We Know It's Working? By Using Trend Analysis RFO to RFO

- Chemistry Parameters
 - **❖** At Power Co-58 and Co-60 trend... Declining?
 - Shutdown Core Release... Declining?
- RP Measurements-Everything Declining?
 - Dose Rates and Effective Dose Rate
 - Personnel Contamination Events (PCE)'s
 - Discrete Radioactive Particles
 - Smearable Contamination Levels
- Low Level Waste and Liquid Effluent Activity
 - Less Low Level Waste
 - Less Curies



CRUD (ref: ANT International presentation)

- Corrosion Products Released from System Surfaces
 - Ionic Forms
 - Particles
 - Colloids (Agglomerating to Particles Given Time)
 - Co-deposited Ions/Colloids/Particles
- Particles and Colloids Deposit on Surfaces by
 - Gravity (big particles) in Low Flow Areas
 - Crud Diffusion and Ion Exchange In Oxide Films
 - Surface Charge Attraction
 - Precipitation at over-saturation due to boiling



CRUD Oxide Forms (ref: ANT International presentation)

- Elemental Nickel
 - Possible to Obtain PWR/VVER at high Hydrogen Concentrations
 - (Also, hydrogen pick-up facilitated in nickel base materials and zirconium alloy cladding)
- Hematite Fe₂O₃
 - Formed at more oxidizing conditions
 - Present in BWRS at NWC at sufficient iron input
- Magnetite Fe₃O₄



- Chromium oxide Cr₂O₃
 - Insoluble in reducing conditions- Soluble in oxidizing?
- Mono Oxides NiO, CoO, ZnO
 - Present in PWRs
 - Probably Present in BWRs



P1: Letdown Piping Before Demineralizer After Non Regenerative HX, 2 inch Sch 40 Stainless Steel (austenitic) CZT Probe, 60 mm3, 6 inch Long



P2: Letdown Piping After Demineralizer Insulated Piping, Dose Rate: 0.334 mR/hr




10,000 s. acquire time Data Showed No pipe wall deposition



Frank Rihls, Chem. Technician

Spent Fuel Pool Piping, Before Pump Dose Rate 4.35 mR/hr



CZT Probe
Location
Dose Rate 4.3 mR/hr



Containment: B Hot Let Piping


Reflective Insulation
Dose Rate Contact = 60 mR/hr





B Cold Leg Piping Probe Was Placed in Box

Dose Rate: 44 mR/hr Contact





875 A Safety Injection Check Valve

No Insulation On pipe

Dose Rate Contact: 150 mR/hr Contact





875 B Safety Injection Check Valve No Insulation On pipe

Dose Rate Contact: 160 mR/hr Contact, 30 cm 80 mR/hr






875 C Safety Injection Check Valve


Dose Rate = 150 mR/hr Contact (9 feet elevated)







World Record- RVH Replacement Low Dose 5.923 REM





Paul_Skinner@ FPL.com
WBacon@scana.com
JHunsicker@scana.com
Kevn.Jepson@nmcco.com
Radwasted@aol.com