


NRC Update on ALARA Activities, Regulatory Discussion

January 9-11, 2017

Steven Garry
Sr. Health Physicist
Radiation Protection and Consequence Branch
Division of Risk Assessment
Office of Nuclear Reactor Regulation

U.S. Commercial LWR Collective Dose 1973 – 2015






Average Measurable Dose per Worker 1973 – 2015








^{*} Not adjusted for transient workers.

Average Number of Workers with Measurable Dose 1973 – 2015







	Plant Name	Three Year Coll. TEDE per Reactor Year 2013-2015 (person-rem)	Percent Change From 2012-2014	2012-2014 Quartile (if changed)
	DUANE ARNOLD	52.947	-42% ▼	2
<u>a</u>	FITZPATRICK	65.356	-43% ▼	3
1st Quartile	DRESDEN 2,3	65.457	0%	-
ğ tı	OYSTER CREEK	66.059	-42% ▼	3
₹	LIMERICK 1,2	66.119	-8% ▼	-
	GRAND GULF	80.812	- 51% ▼	4
	CLINTON	81.427	52% ▲	1
<u>e</u>	HATCH 1,2	82.877	-5% ▼	-
uarti	QUAD CITIES 1,2	86.392	-4% ▼	-
2nd Quartile	COOPER STATION	88.725	-49% ▼	4
2n	NINE MILE POINT 1,2	106.858	-28% ▼	3
	SUSQUEHANNA 1,2	109.026	5% ▲	-
	RIVER BEND 1	110.987	40% 🔺	1
rtile	BROWNS FERRY 1,2,3	117.836	-14% ▼	-
3rd Quartile	HOPE CREEK 1	118.991	5% ▲	-
3rd	MONTICELLO	121.444	33% 🔺	2
	PILGRIM	143.779	84% 🔺	1
	FERMI 2	153.577	24% 🔺	3
<u> </u>	BRUNSWICK 1,2	165.487	0%	-
4th Quartile	COLUMBIA GENERATING	182.257	80% 🛦	2
h Q	LASALLE 1,2	208.635	28% ▲	-
4	PEACH BOTTOM 2,3	218.412	7% ▲	-
	PERRY	281.701	68% ▲	-
	Average per Reactor-Year	119.813	1% ▲	



Three-Year
Collective
TEDE per
Reactor-Year
for BWRs
2013–2015

< Average 119.813

White threshold > 240 rem

		Plant Name	Three-Year Coll. TEDE per Reactor Year 2013-2015 (person-rem)	Percent Change From 2012-2014	2012-2014 Quartile (if changed)
		BRAIDWOOD 1,2	21.135	-48% ▼	2
		PALO VERDE 1,2,3	23.523	-1% ▼	-
		FARLEY 1,2	24.476	22% 🔺	-
	1st Quartile	DIABLO CANYON 1,2	25.602	10% 🔺	-
		CALLAWAY 1	27.808	-2% ▼	-
		CALVERT CLIFFS 1,2	28.128	-29% ▼	2
		GINNA	28.659	-26% ▼	2
		SOUTH TEXAS 1,2	29.718	24% 🔺	-
		BYRON 1,2	30.236	-4% ▼	-
		COOK 1,2	31.233	-9% ▼	-
		OCONEE 1,2,3	31.608	-18% ▼	-
		WATTS BAR 1	31.735	2% ▲	1
	<u>e</u>	BEAVER VALLEY 1,2	33.312	-13% ▼	-
	arti	SALEM 1,2	33.812	-6% ▼	-
	gn	COMANCHE PEAK 1,2	37.895	-9% ▼	-
	2nd Quartile	HARRIS	38.042	-16% ▼	3
	2r	CATAWBA 1,2	38.560	1% ▲	-
		NORTH ANNA 1,2	39.593	-21% ▼	3
		POINT BEACH 1,2	39.690	-9% ▼	3
		ARKANSAS 1,2	43.055	56% ▲	1
		SEQUOYAH 1,2	43.148	-37% ▼	4
	<u>o</u>	PRAIRIE ISLAND 1,2	43.882	-18% ▼	4
	3rd Quartile	TURKEY POINT 3,4	45.944	-37% ▼	4
	ğ	WATERFORD 3	46.139	-58% ▼	4
	<u>p</u>	SEABROOK	46.159	44% 🔺	1
	က	INDIAN POINT 2,3	46.165	-15% ▼	4
		MILLSTONE 2,3	48.112	-3% ▼	-
		FORT CALHOUN	48.298	34% ▲	2
	tile	VOGTLE 1,2	49.268	0%	3
		MCGUIRE 1,2	49.513	-4% ▼	3
		SURRY 1,2	51.333	5% ▲	3
		ROBINSON 2	55.211	-5% ▼	-
	uar	SUMMER 1	60.333	-9% ▼	-
	4th Quartile	ST. LUCIE 1,2	64.018	1% 🔺	-
		DAVIS-BESSE	68.006	-17% ▼	-
		WOLF CREEK 1	71.187	46% 🔺	3
		THREE MILE ISLAND 1	103.251	105% 🔺	3
		PALISADES	244.193	-2% ▼	-
		Average per Reactor-Year	43.540	-8% ▼	



Three-Year Collective TEDE per Reactor-Year for PWRs 2013–2015

Average 43.540

White threshold > 135 rem



Individual Worker Dose



- Performance indicator (PI) program applies to an individual's unintended dose or unauthorized entry into locked high radiation area
- NEI 99-02, Rev. 6, Regulatory Assessment Performance Indicator Guideline
- Examples: dose or dose rate alarm
 - evaluated under the performance indicator program
 - more than 100 mrem unintended dose is PI occurrence
 - unauthorized entry into a locked high radiation area
 - NRC expects licensees to use corrective action program to the fix problems

NRC Focus



- Focus is not on the industry "averages"
- Focus is not on any one "individual's dose"
- ALARA focus is on the collective dose for "individual plants" and "individual jobs"
- Significance of finding is assessed as Minor, Green, White, Yellow, Red

NRC Inspection of ALARA



- ALARA planning is an inspectable area under the ROP: Inspection Procedure 71124.02 (Revised 2016)
 - radiological work planning
 - verification of dose estimates
 - implementation of ALARA work controls
 - radiation worker performance
 - corrective actions (Problem Identification and Resolution)
- Three-year averages
 - quartiles used in planning inspection hours
 - collective dose used in inspection findings

Collective Dose




- ALARA compliance is based on collective dose
- Compliance is not based on whether individual doses are the absolute minimum, or use of all possible ALARA methods
- Green findings are based on exceeding 5 rem and 50% above estimates
- White findings are based on exceeding 25 rem

ALARA Issue Screening



- ALARA Findings: performance deficiencies that concern unplanned, unintended occupational collective dose
- Performance Deficiency: Failure to meet a requirement or self-imposed standard where the cause was reasonably within the licensee's ability to foresee and correct



Significance Determination



- If three year average for:
 - PWR ≤ 135 rem PWR,
 - BWR ≤ 240 rem,
 - Significance is always "Green"
- If three year average is > 135 rem PWR, or > 240 rem BWR:
 - Is actual dose > 25 rem AND > 50% of the estimate?
 - No, then a Green finding
 - Yes, then a White finding, or
 - Were there more than 4 jobs where actual dose > 5 rem and > 50% above dose estimate?
 - No, then a Green finding
 - Yes, then a White finding

NRC Findings



NRC inspections every 2 years

5 findings in last 2 years at 65 sites

Palisades



1st quarter, 2014 ML14127A543

- Control rod drive mechanism housing work
- Estimated dose was ~3 rem, actual dose was 26.5 rem, emergent work dose was 8.5 rem
- Problems:
 - Re-work of ultrasonic testing exams due to insufficient or inadequate initial exams,
 - Re-work of shielding poor coordination of installation and removal re-work, and
 - Inadequate mock-up testing
- Green because 3 yr collective dose was < 135 rem (at the time of the inspection finding)

Indian Point – Unit 2

3rd quarter, 2014 ML14314A052



- Reactor coolant pump work activities
 - estimate 7.3 rem, actual 13.7 rem
 - dose rates were 25 percent higher because crud burst was 6.7 uCi/cc (4 times higher than planned) and clean-up levels were not reduced to planned clean-up criteria
 - Some work was performed inside bioshield instead of on refueling floor which added 2.5 person-rem
 - failed to install temporary shielding prior to the start of work added ~1 rem; and
 - pump coupling rework and realignment added ~0.5 rem

Fermi



4th quarter, 2014 ML15029A206

- Refuel activities including core alterations, bridge repair, local power range monitor replacement, fuel sipping
 - estimated 3.7 rem, actual 15.3 rem
 - estimated 9,070 hrs, actual 20,462 hrs
 - Problems:
 - increased radiation levels due to a crud burst
 - conflicts and delays with refueling equipment,
 - procedural challenges,
 - equipment malfunctions
- Lack of observing & coaching
- In-progress review performed at 80% (too late)

Millstone

U.S.NRC

United States Nuclear Regulatory Commission

Protecting People and the Environment

4th quarter, 2014 ML15042A160

- Deficiencies in planning and work control while performing scaffolding work, valve maintenance, and a valve replacement
- Dose
 - Scaffolding 11.8 rem estimate, 17.7 rem actual dose
 - valve maintenance 5.5 rem estimate, 10.2 rem actual dose
 - valve replacement 5.9 rem estimate, 11.6 rem actual dose
- Scaffold interferences between adjacent jobs
- Poor sequencing of work, work size control, inadequate exposure tracking, and poor pre-outage planning
- Disconnect ALARA planners did not attend outage planning meetings

Columbia

2nd quarter, 2015 ML15219A143



- Alternate Fuel Pool Cooling Modification
- Estimated 11.1 rem, actual 17.8 rem
- Unplanned, unintended dose > 50% of estimate
- Problems:
 - Delays in installing shielding & elevated dose rates
 - Lack of in-field welding expertise and supervisory oversight led to re-work
 - Not using low-dose waiting areas
 - In-progress reviews not done in timely manner



Questions and Discussion