

Point Lepreau Refurbishment ALARA / RP Update

Charles Hickman
Manager, Health Safety and Environment
ISOE Symposium
Florida, 2010

A V I T A L P A R T O F N E W B R U N S W I C K



Énergie NB Power

Nucléaire Nuclear




Agenda

- NB Power
- Project overview
- Statistics
- OPEX / Lesson learned
- Program improvements
- Successes
- Conclusions




NB Power Grid

- Generating capacity:
3959 MW
- Fuels
 - Nuclear, Oil, Coal, Gas
Orimulsion®, Hydro and
Diesel
- NB Power Nuclear
 - Single Unit
 - CANDU 6 (635 MW)
 - 685 employees
 - 30 % electricity need




Top Priority

- Safety is our top priority
 - Integrated joint health and safety committee with all on-site contractors and NB Power
 - Continue to maintain some of the highest standards for health, safety and training throughout refurbishment and beyond
 - High degree of ownership of standards for safety and training by all contractors



How a CANDU Works




Phases of Refurbishment

- 1999 – 2005
 - Project Planning
- 2005
 - Project approval
- 2008 - Phase I
 - Shutdown the plant
 - Defueling of the reactor
 - Preparation of work isolation
- Phase II
 - Execution of the outage work
- Phase III
 - Commissioning
 - Return to service




Retube Activities

- Feeder removal and installation
- Fuel channel removal and installation
 - Pressure tubes and calandria tubes



Retube Activities

- Upper feeder installation in progress ↱



Statistics

Average number of PAD entries per day

- 1000 – 1200

- Number of people on dose records

- 3500

- Personal dose to date - (demolition)

- 90% less than 2.0 mSv (2 rem)

- 99% less than 4.5 mSv (4.5 rem)

- Internal dose

- Approximately 1-3% of whole body dose



OPEX / Lessons Learned

- Many lessons learned
 - Early decisions with ALARA implications
 - Organizational issues
 - Tooling issues
 - Contractor management issues
 - Program issues



Early ALARA Decisions

- Source Term Management
 - Conscious decision not to decontaminate (CANDECON or other)
 - › Concern about damage to balance of heat transport system
 - › Concern about waste management
- Feeder removal
 - Originally planned to remove lower section only
 - Decided to remove entire feeder
 - › Concern about future inspections
 - › Removed source term
 - › Created welding challenges



Organization

- NBPN and AECL radiation protection programs were separate and independent
 - Now integrated, excellent team work
 - Many seconded resources
- Initial planning for Protection Assistants was based on equipment working at full capacity and activities generally proceeding sequentially
 - Underestimated requirements
- NB Power Nuclear (NBPN) and Atomic Energy Canada Limited (AECL) worked together to provide additional resources and a radiation protection structure to address the increased requirements
 - Significant cost implications



Protection Assistants / Use of AVTS

- Challenges to Protection Assistant support
 - AVTS used but did not reduce number of PAs required
 - Outage extension challenging the PA resources
 - Trained significant number of yellow qualified staff
 - › Helped PAs, but significant draw on training staff
- Mentoring provided by experienced staff
- Yellow and green qualified individuals have gained significant on the job experience
- Many people have moved from yellow to green based on experience gained (accelerated progression)
 - No neutrons, minimal tritium
- Although occasional challenges, excellent overall performance especially given the hazards



Tooling Development and Operation

- Significant use of large mock up training facility
 - Definite benefits
 - Did not prevent tooling issues in the field
- Feeder removal
 - Tool issues led to initial delays, modified process
 - Task completed under dose budget by using new process
 - New process led to contamination challenges
- End Fitting Removal
 - Slower than expected
 - Parallel work activities, open beam work
 - No significant issues
- Pressure Tube Removal
 - Very significant fields (Sv/h fields, mSv/h contamination)
 - Significant tooling challenges
 - PA intensive
 - Generally well planned and executed



Tooling

- Radiography
 - Potentially 2000-2500 welds requiring radiography
 - Significant risk and potential dose
- Phased array
 - AECL developed and got system approved
- Technical challenges
 - Phased array showed “more” than radiography
 - Needed to disposition differences
 - Many re-welds



Contamination Control and Monitoring

- Scrubs
 - Implemented washable scrubs at start of outage
 - New change facilities, new cafeteria facilities
 - Increased traffic
 - › Never had accurate estimate of manpower loading, total number of workers
- Inter-zonal monitoring
 - Increased capabilities at start of outage
 - Installed intra-zonal monitoring (in Zone 3)
 - Staffed last barrier to improve behaviours
- Unexpected alpha contamination
 - Additional monitoring, dedicated clean up effort
- Given nature of work, issues well managed



Contractor Management

- Nuclear is different
 - Many workers did not understand why, did not have “nuclear” awareness
 - Significant challenge to provide sufficient and appropriate oversight to contractor staff
- Watershed event
 - Stuck pressure tube stub prevented proper closing of waste container lid
 - Lack of assessment and planning when resolving issue
 - Issues that led to cause of stuck pressure tube stub and lack of planning investigated and corrected
- Subsequent activities
 - Developed specific procedures / protocols for unplanned high hazard work
 - Greater awareness of hazards and understanding of requirements of working in the nuclear field
- Oversight / Oversight / Oversight ...



Programmatic Improvements

- Volume of work and number of people doing radiation work required program improvements:
 - Bioassays – improved system to “flip flags”
 - Contamination control – attendant at the whole body monitors have addressed issues
 - Rubber areas – weekly rubber area inspections
 - Housekeeping – expectations being pushed, contractors cooperating
 - Waste management – new bags being implemented to help in field
 - Dosimetry – staff at reactor building entrance to provide added attention, improvements to PAD sign-out system
 - Second dose desk at personnel airlock



Dose Summary

- Pre-outage estimate 8.3 Sv
 - Based on main activities, no detailed estimate for “other” or “non critical path” activities
- Current estimate 11.3 Sv
- Difference:
 - Schedule delays
 - Improved details and estimates for “other work”
 - Reflects contingency work



Recent High Hazard Work Successes

- Volume Reduction System (VRS) Maintenance
 - High hazard work
 - Optical sensor (lots of debris)
 - Dealing with inconel garter springs, dose rates up to 10 Sv/h (1000 rem/h)
 - Removal of 7 Sv/h (700 rem/h) dust from VRS, dose received 117uSv (11.7 mrem)
 - Replaced VRS waste chute (1.1 mSv (110 mrem))
 - › planning included mock-up, which improved performance
 - OPEX for calandria tube removal phase
- Dismantling of volume reduction system
 - Detailed planning and mock-up
 - Used experienced team
 - Fields of up to 20 Sv/h (2000 rem/h), lots of contamination potential
 - Budget of 8 mSv (800 mrem), expended 6.4 mSv (640 mrem)
 - No contamination spread



Conclusions

- Radiation Protection and ALARA team has overcome many challenges
- Contract staff matured to understand “Why nuclear is different”
- Challenges require staff to work with unprecedented radiation fields and contamination
 - ALARA respected, no overexposure or significant loss of contamination control
- There are still many opportunities for improvement within the RP program
- We continue to stay focused on the most important issues while working to address the low level issues

